STUART GROUP LTD

Used Generator Information

T: 01953 454540 F: 01953 456968
E: enquiries@stuartgroup.info
W: www.stuartgroup.ltd.uk
Stuart House, Hargham Road, Shropham, Norfolk, NR17 1DT

Asset Data Information

Stock Number	XP150017
Set Manufacturer	FG Wilson
Set Model	P1500

Alternator Data

kVA - Prime	1500
kW - Prime	1200
kVA - Standby	1650
kW - Standby	1320
Volts	415
Hz	50
Amps @ Standby rating	2293
Make	Leroy Somer
Model	LL8124P
Serial No:	184053/02
RCD	No
MCB | ACB	MCB 3 Pole
PMG | AREP	PMG
Heater	No

Engine Data

Make	Perkins
Model	4012 TAG 2A
Serial No:	DGB122051U8199M
Hours	440
Exhaust Type	Box on roof
Bellows	Yes
Voltage	24
Batteries / Battery Type	4 x Lead Acid
Battery Isolator	No
Water Jacket Heater	Yes
Lube oil top up	Yes
Racor Filter	No
3 Way Fuel Valve	No
Fire Drop Valve	Yes

Fuel Tank Data

Skid / Free Standing	No
Single Skin / Bunded	
Capacity Litres	
Capacity Hours @ 75%	
Fuel Gauge	
Transfer Pump	

Set Serial Number	FGWPST02PV0A00975
Year Of Manufacture	2005
Price	£79,500.00
Date Into Stock	July 2023

Enclosure Data

Open / Skid	Skid
Sound Attenuated	Yes
Containerised	No
Sound Level 75% @ 7m	
Length mm	11890
Width mm	3300
Height mm (excl exhaust)	3700
Height mm (incl exhaust)	3850
Colour	Green
Condition	Good
Lighting AC / DC	AC
Bunded Floor	Yes

Lifting Data / Chassis

Weight - Kg	30000
Centre Point	No
Corner Lifting Points	Yes, on chassis
Forklift Pockets	No
Trailer	No

Control Panel Data

Make	Genpart 6400
LED / Analog	LED
Hour Meter	Yes
Oil	Yes
Water	Yes
Battery	Yes
Amp	Yes
Volts	Yes
Hz	Yes
AMF - Parallel	Parallel
Battery Charger	Yes

Additional Data

Sockets	No

Warranty

FG WILSON Authorised Dealer

All Diesel Generators Are Inspected And Tested Prior To Dispatch